

IVY SUBDIVISION

ENDCLIFFE ROAD
KENNEBUNKPORT, MAINE


APPLICANT:

IVY THREE, LLC
2 LIVEWELL DRIVE, SUITE 203
KENNEBUNK, ME 04043


**ENGINEER/SURVEYOR/
LANDSCAPE ARCHITECT:**



WWW.SEBAGOTECHNICS.COM
75 John Roberts Rd.
Suite 4A
South Portland, ME 04106
Tel. 207-200-2100




SCALE: 1" = 100'



LOCATION MAP

SHEET INDEX

SHEET NO.	SHEET TITLE
1	COVER SHEET
2	SECOND AMENDED SUBDIVISION PLAN
3	PLAN AND PROFILE - ENDCLIFFE ROAD
4	UTILITY CONNECTION PLAN
5	UTILITY CONNECTION PROFILE
6	EROSION CONTROL NOTES
7	DETAILS
8	DETAILS
1 OF 2	PRE-DEVELOPMENT WATERSHED PLAN
2 OF 2	POST-DEVELOPMENT WATERSHED PLAN



NOT FOR
CONSTRUCTION

REV.	BY	DATE	STATUS
C	SGD	03/30/2021	ISSUED FOR FINAL SUBDIVISION REVIEW
B	SGD	02/02/2021	REVISED BY TOWN AND PUBLIC INPUT
A	SGD	10/28/2020	ISSUED TO PLANNING BOARD FOR MAJOR REVISION REVIEW

THIS PLAN SHALL NOT BE MODIFIED WITHOUT WRITTEN PERMISSION FROM SEBAGOTECHNICS, INC. ANY ALTERATIONS, AUTHORIZED OR OTHERWISE, SHALL BE AT THE USER'S SOLE RISK AND WITHOUT LIABILITY TO SEBAGO TECHNICS, INC.




COVER SHEET
OF:
IVY SUBDIVISION
ENDCLIFFE ROAD
KENNEBUNKPORT, MAINE
FOR:
IVY THREE, LLC
2 LIVEWELL DRIVE, SUITE 203
KENNEBUNK, ME 04043

DESIGNED	SAH
DRAWN	STI
CHECKED	SGD
DATE	4/13/2020
SCALE	1" = 100'
PROJECT	10234


10234_C:\wp\TAB\24x36

STEPHEN G. DOE, R.L.A. 131

03/30/21



VERNAL POOL AREA CALCULATIONS:
 TOTAL AREA WITHIN 250' VERNAL POOL SETBACK (SUBJECT PARCEL ONLY) = 154,343
 EXISTING DEVELOPED AREA IN VERNAL POOL SETBACK = 0.0 S.F.
 PROPOSED DEVELOPMENT IN VERNAL POOL SETBACK = 38,430 S.F.
 38,430/154,343 S.F. = 24.9%
 IMPACT IS 24.9% OF SETBACK AREA



GENERAL NOTES:

- THE RECORD OWNER OF THE PARCEL IS: IVY THREE, LLC BY DEEDS RECORDED IN THE YORK COUNTY REGISTRY OF DEEDS (YCRD) IN BOOK 15979, PAGES 738-741 AND IN BOOK 15979, PAGES 738-741.
- THE PROPERTY IS SHOWN AS: PARCEL C, LOT 18, BLOCK 13 ON THE TOWN OF KENNEBUNKPORT TAX ASSESSOR'S TAX MAP NO. 7, AND IS LOCATED IN THE CAPE ARUNDEL ZONE.
- SPACE AND BULK CRITERIA FOR THE CAPE ARUNDEL ZONE ARE AS FOLLOWS:
 MIN. NET RESIDENTIAL AREA PER DWELLING: 40,000 S.F.
 MIN. LOT SIZE: 40,000 S.F.
 MIN. LOT FRONTAGE: 100'
 MIN. FRONT YARD: 20' **30'
 MIN. SIDE YARD: 15' **20'
 MIN. REAR YARD: 15' **20' ***30'
 MAX. BUILDING HEIGHT: 35'
 MAX. LOT COVERAGE: 20%
 MIN. OPEN SPACE: 20%
 * SEE ORDINANCE FOR MORE PARTICULAR INFORMATION
 ** DEED RESTRICTIONS, SEE GENERAL NOTE 1 FOR REFERENCE
 *** 30' SETBACK FOR EASTERN SIDE LINE OF LOT 2B ONLY.
- RESIDENTIAL AREA CALCULATION:**
 TOTAL PARCEL AREA = 341,939 s.f.
 LESS 15% FOR ROADS = 51,290 s.f.
 LESS 15% FOR OPEN SPACE = 51,290 s.f.
 LESS WETLANDS = 39,967 s.f.
 LESS EASEMENTS (ROW) = 30,346 s.f.
 NET RESIDENTIAL AREA = 199,392 s.f.
 NET RESIDENTIAL DENSITY = 199,392 S.F. / 40,000 S.F. = 5 LOTS
 TOTAL LOTS PROPOSED = 2 LOTS
LOT SUMMARY:
 LOT 2A AREA = 141,677 s.f.
 LESS WETLANDS = 29,428 s.f.
 LESS EASEMENTS = 16,849 s.f.
 NET LOT AREA = 95,400 s.f.
 LOT 2B AREA = 114,108 s.f.
 LESS WETLANDS = 3,610 s.f.
 LESS EASEMENTS = 1,997 s.f.
 LESS ROW = 20,163 s.f.
 NET LOT AREA = 88,638 s.f.
 OPEN SPACE (REQUIRED):
 TOTAL AREA REQUIRED (15% OF 341,939 s.f.) = 51,291 s.f.
 UPLAND AREA REQUIRED (1/3 OF 51,291 s.f.) = 17,097 s.f.
 OPEN SPACE (PROVIDED):
 TOTAL AREA PROVIDED = 86,153 s.f.
 LESS WETLANDS = 64,669 s.f.
 LESS EASEMENTS = 0 s.f.
 NET OPEN SPACE AREA = 21,484 s.f.
- BOUNDARY AND TOPOGRAPHIC INFORMATION SHOWN HEREON IS BASED UPON AN ON THE GROUND SURVEY PERFORMED BY SEBAGO TECHNICS, INC. IN AUGUST OF 2010, AND PRIOR SURVEY WORK BY SEBAGO TECHNICS, INC. IN ACCORDANCE WITH THE STATE OF MAINE BOARD OF LICENSURE FOR PROFESSIONAL LAND SURVEYORS STANDARDS OF PRACTICE WITH THE EXCEPTION THAT NO REPORT OF SURVEY HAS BEEN PREPARED. NO NEW LEGAL DESCRIPTION HAS BEEN SET AT THE ISSUANCE OF THIS PLAN AND THAT THE WETLAND AREAS SHOWN HEREON WERE DELINEATED BY SOMEONE OTHER THAN THE SIGNING PROFESSIONAL.
- PLAN REFERENCES:
 A. DIVISION OF LAND PLAN OF OLD FORT INN, KENNEBUNKPORT, MAINE FOR IVY ONE, LLC, IVY TWO, LLC & IVY THREE, LLC BY SEBAGO TECHNICS, INC., DATED AUGUST 23, 2010 AND RECORDED IN THE YCRD IN PLAN BOOK 346, PAGE 36.
 B. RESUBDIVISION PLAN FOR CAPE ARUNDEL WOODS ON ENDCLIFFE ROAD IN KENNEBUNKPORT, MAINE FOR ROBERT J. WASKIEWICZ & PORTER HOLDINGS, INC. BY WAYNE DESPER DATED SEPTEMBER 24, 1993 AND RECORDED IN THE YCRD IN PLAN BOOK 216, PAGE 46.
 C. SUBDIVISION PLAN OF IVY SUBDIVISION, DOVER LAKE, KENNEBUNKPORT, MAINE FOR IVY THREE, LLC BY SEBAGO TECHNICS, INC. DATED 06-30-11 WITH REVISION DATE 03-19-12 AND RECORDED IN THE YCRD IN PLAN BOOK 355, PAGE 03.
- PLAN ORIENTATION IS GRID NORTH, MAINE STATE PLANE COORDINATE SYSTEM, WEST ZONE 1802NAD83. ELEVATIONS SHOWN HEREON ARE BASED UPON NATIONAL GEODETIC VERTICAL DATUM OF 1929 (NGVD 29) BASED ON DUAL FREQUENCY GPS OBSERVATIONS.
- UTILITY INFORMATION DEPICTED HEREON IS COMPILED USING PHYSICAL EVIDENCE LOCATED IN THE FIELD. UTILITIES EXISTING HEREON MAY NOT NECESSARILY REPRESENT ALL EXISTING UTILITIES. CONTRACTORS NEED TO CONTACT DIG-SAFE SYSTEMS, INC. (1-888-DIG-SAFE) AND FIELD VERIFY EXISTING UTILITIES PRIOR TO CONSTRUCTION AND/OR EXCAVATION.
- THE LOCUS PROPERTY AS DEPICTED HEREON DOES NOT FALL WITHIN A SPECIAL FLOOD HAZARD AREA AS DELINEATED ON THE FLOOD INSURANCE RATE MAP FOR KENNEBUNKPORT, MAINE, YORK COUNTY, COMMUNITY-PANEL NUMBER 230170 0003 B, HAVING AN EFFECTIVE DATE OF APRIL 18, 1983. THE LOCUS FALLS WITHIN AN AREA IDENTIFIED AS ZONE C.
- LOTS 2A & 2B WILL BE SERVED BY PUBLIC SEWER, AND PUBLIC UNDERGROUND ELECTRIC, TELEPHONE AND CABLE. LOT 2A WILL BE SERVED BY PUBLIC WATER. LOT 2B WILL BE ON A WELL.
- WAIVER REQUESTS: SUBDIVISION REGULATIONS
 A. ARTICLE 12.2.B.2.f - MAXIMUM ROAD LENGTH TO HAMMERHEAD TURNAROUND TO BE APPROXIMATELY 1,200 FT FROM THE TERMINUS AT OCEAN AVENUE WAIVER GRANTED MARCH 3, 2021.
 B. ARTICLE 12.2.B.2.g - CENTERLINE OF ROAD TO FOLLOW EXISTING ROAD BE VERSUS CENTERLINE OF RIGHT-OF-WAY. WAIVER GRANTED MARCH 3, 2021.
 C. ARTICLE 12.2.B.2.j - SIDEWALKS NOT REQUIRED. WAIVER GRANTED MARCH 3, 2021.
 D. ARTICLE 12.2.B.2.k - CURBING NOT REQUIRED. WAIVER GRANTED MARCH 3, 2021.
 E. ARTICLE 12.2.B.2.l - ROADWAY WIDTH TO BE 14 FT WITH 4 FT WIDE SHOULDERS (22 FT TOTAL WIDTH) REDUCED TO 18 FT TOTAL WIDTH IN DESIGNATED TWO SECTIONS DUE TO EXTENSIVE LEDGE OUTCROPS. WAIVER GRANTED MARCH 3, 2021.
 F. ARTICLE 12.2.B.2.m - ROADWAY WIDTH TO BE 14 FT WITH 4 FT WIDE SHOULDERS (22 FT TOTAL WIDTH) REDUCED TO 18 FT TOTAL WIDTH IN DESIGNATED TWO SECTIONS DUE TO EXTENSIVE LEDGE OUTCROPS. WAIVER GRANTED MARCH 3, 2021.
- WETLANDS SHOWN ON THIS PLAN WERE FIELD DELINEATED BY GARY FULLERTON OF SEBAGO TECHNICS, INC. IN OCTOBER 2004 AND FIELD LOCATED BY CONTROLLED SURVEY.
- ALL ROADS IN THIS SUBDIVISION SHALL REMAIN PRIVATE ROADS TO BE MAINTAINED BY THE DEVELOPER OR THE LOT OWNERS.
- THE LOCUS PROPERTY IS SUBJECT TO THE FOLLOWING:
 A. AN EASEMENT TO CENTRAL MAINE POWER CO. AND NEW ENGLAND TELEPHONE AND TELEGRAPH CO. TO CONSTRUCT, REBUILD, MAINTAIN POLE LINES ALONG, OVER, AND ACROSS ALL PREMISES OWNED BY GRANTOR, EXTENDING IN ALL DIRECTIONS AND WAYS WHICH MAY BE LAID OUT OR ESTABLISHED IN THE FUTURE.
 B. THE PARCEL HEREON IS CONVEYED SUBJECT TO ALL OF THE COVENANTS, CONDITIONS, AND RESTRICTIONS AS SET FORTH IN A WARRANTY DEED FROM SEA SHORE ASSOCIATES TO EARL F. ADAMS AND K. BLAIR HODGE.
 C. ALSO CONVEYING ALL RIGHT, TITLE AND INTEREST IN A CERTAIN STRIP OF LAND KNOWN AS ENDCLIFFE ROAD SUBJECT TO SUCH RIGHTS, IF ANY, THE INHABITANTS OF THE TOWN OF KENNEBUNKPORT OR OTHERS MAY HAVE IN SAID ROAD.
 D. THE LOCUS PROPERTY IS BENEFITED BY THE FOLLOWING:
 A. COVENANTS TO THE GRANTEE, WITHOUT WARRANTY COVENANTS, QUITCLAIM COVENANTS, OR COVENANTS OF ANY NATURE, THE RIGHT TO PASS AND REPASS BY AND FOOT ON EXISTING ROADS AND WAYS WHICH ANY OF THE REAL PROPERTY HEREIN CONVEYED ABUTS. THE COST OF MAINTENANCE OF PRIVATE ROADS AND WAYS SHALL BE SHARED EQUALLY BY ADJOINING LOT OWNERS.
 E. THE ELEVATIONS SHOWN HEREON ARE BASED UPON NATIONAL GEODETIC VERTICAL DATUM OF 1929 (NGVD 29) ESTABLISHED UTILIZING AN TOPCON HIPER / LEGACY E DUAL FREQUENCY GPS RECEIVERS POST PROCESSED USING BASELINE DATA FROM THREE CONTINUOUSLY OPERATING REFERENCE STATIONS (CORS) LOCATED IN THE NORTHERN NEW ENGLAND REGION AND WAS DERIVED FROM THE GEOID-2003 MODEL OF THE U.S. AND COMPARED WITH A LOCAL THIRD ORDER BENCHMARK IN THE AREA.
 F. THE HORIZONTAL DATUM SHOWN HEREON IS BASED ON THE MAINE EAST ZONE (1801) DEFINED BY THE NORTH AMERICAN DATUM OF 1983 (NAD 83).
 G. THERE SHALL BE NO CONVEYANCE OF ANY LOT OR ISSUANCE OF ANY BUILDING PERMIT UNTIL A PERFORMANCE GUARANTEE(S) COVERING THE COST OF ALL REQUIRED IMPROVEMENTS IS SUBMITTED AND APPROVED BY THE TOWN OF KENNEBUNKPORT.
 H. THE DEVELOPMENT IS SUBJECT TO THE FINDINGS OF FACTS, CONCLUSIONS, DECISIONS AND CONDITIONS OF APPROVAL AS APPROVED BY THE TOWN OF KENNEBUNKPORT PLANNING BOARD AND RECORDED IN THE YORK COUNTY REGISTRY OF DEEDS.
 I. ALL STORM DRAIN PIPING SHALL COMPLY WITH TOWN SPECIFICATIONS.
 J. LOT 2A SHALL PROVIDE A DRIVEWAY HAMMERHEAD TURNAROUND ON THE LOT WITHIN 100' TO 200' FROM THE BUILDING WHICH WILL ACCOMMODATE A FIRE LADDER TRUCK. SIZE AND LOCATION OF TURNAROUND TO BE APPROVED BY THE FIRE CHIEF PRIOR TO ISSUANCE OF A BUILDING PERMIT.
 K. LOTS 2A AND 2B SHALL BE RESTRICTED TO 1 SINGLE FAMILY RESIDENCE ON EACH LOT.
 L. LAND DISTURBANCE AND CLEARING OF VEGETATION SHALL BE LIMITED TO THE BUILDING AREA NOTED ON PLAN. CLEARING BEYOND THIS LIMIT WILL REQUIRE PLANNING BOARD APPROVAL AND APPROVAL FROM MAINE DEP FOR VERNAL POOL IMPACTS.

LEGEND

EXISTING	PROPOSED
PROPERTY LINE/R.O.W.	PROPERTY LINE/R.O.W.
ABUTTER LINE/R.O.W.	ABUTTER LINE/R.O.W.
SETBACK	SETBACK
EASEMENT	EASEMENT
CENTERLINE	CENTERLINE
MONUMENT	MONUMENT
IRON PIPE/ROD	IRON PIPE/ROD
ZONE LINE	ZONE LINE
TEST PIT	TEST PIT
BUILDING	BUILDING
DECK/STEPS/OVERHANG	DECK/STEPS/OVERHANG
EDGE WETLAND	EDGE WETLAND
WETLANDS	WETLANDS
STREAM	STREAM
LEDGE	LEDGE
EDGE PAVEMENT	EDGE PAVEMENT
EDGE GRAVEL	EDGE GRAVEL
TREELINE	TREELINE
CONTOURS	CONTOURS
DECIDUOUS TREE	DECIDUOUS TREE
CONIFEROUS TREE	CONIFEROUS TREE

TOTAL WETLAND IMPACTS = 5,564 S.F.

THE PURPOSE OF THIS SECOND AMENDED SUBDIVISION PLAN IS TO CREATE 2 LOTS PLUS COMMON LAND FOR REMAINING LAND OF IVY THREE, LLC.

APPROVAL-TOWN OF KENNEBUNKPORT PLANNING BOARD

DATE _____

CHAIRPERSON _____

STATE OF MAINE, YORK COUNTY SS, REGISTRY OF DEEDS

RECEIVED _____ 20____
 AT _____ M _____ M AND _____

RECORDED IN _____
 PLAN BOOK _____ PAGE _____

ATTEST: _____ REGISTER

DESIGNED SAH
 DRAWN STI
 CHECKED SGD
 DATE 4/13/2020
 SCALE 1" = 50'
 PROJECT 10234

SHEET 2 OF 8

10234 SS (S) 06-17-2020 7:42:24 AM

ISSUED FOR FINAL SUBDIVISION REVIEW
 REVISED BY TOWN AND PUBLIC INPUT
 ISSUED TO PLANNING BOARD FOR MAJOR REVISION REVIEW

STATUS: _____

RECORD OWNER: IVY THREE, LLC
 2 LIVEWELL DRIVE, SUITE 203
 KENNEBUNKPORT, ME 04043

DESIGNED SAH
 DRAWN STI
 CHECKED SGD
 DATE 4/13/2020
 SCALE 1" = 50'
 PROJECT 10234


SHEET 2 OF 8

NOT FOR CONSTRUCTION


SEBAGO TECHNICS, INC.
 75 John Roberts Rd.
 South Portland, ME 04106
 Tel: 207-250-2100

WWW.SEBAGOTECHNICS.COM


CHARLES D. MARCHESE, PLS 0020



ENDCLIFFE - PLAN VIEW
SCALE: HORZ. 1" = 20'




KEYMAP
SCALE: HORZ. 1" = 200'



ENDCLIFFE - PROFILE
SCALE: HORZ. 1" = 20'
VERT. 1" = 2'

LEGEND

EXISTING	PROPOSED
--- PROPERTY LINE/R.O.W.	--- PROPERTY LINE/R.O.W.
▨ BUILDING	▨ BUILDING
--- EDGE WETLAND	--- EDGE WETLAND
--- WETLANDS	--- WETLANDS
--- UPLANDS	--- UPLANDS
--- LEDGE	--- LEDGE
--- EDGE GRAVEL	--- EDGE GRAVEL
--- TREELINE	--- TREELINE
--- 120' CONTOURS	--- 120' CONTOURS
--- 118' CONTOURS	--- 118' CONTOURS
--- 120.00 SPOT GRADE	--- 120.00 SPOT GRADE
--- FILTER BARRIER	--- FB



CHRISTOPHER TAYLOR, P.E. 16677
 STATE OF MAINE
 PROFESSIONAL ENGINEER
 LICENSE NO. 16677
 TAYLOR
 CHRISTOPHER

NOT FOR CONSTRUCTION

REV.	BY	DATE	STATUS
C	SGD	03/30/2021	ISSUED FOR FINAL SUBDIVISION REVIEW
B	SGD	02/02/2021	REVISED BY TOWN AND PUBLIC INPUT
A	SGD	10/26/2020	ISSUED TO PLANNING BOARD FOR MAJOR REVISION REVIEW

THIS PLAN SHALL NOT BE MODIFIED WITHOUT WRITTEN PERMISSION FROM SEBAGO TECHNICS, INC. ANY ALTERATIONS, AUTHORIZED OR OTHERWISE, SHALL BE AT THE USER'S SOLE RISK AND WITHOUT LIABILITY TO SEBAGO TECHNICS, INC.

SEBAGO TECHNICS
 WWW.SEBAGOTECHNICS.COM
 75 John Roberts Rd.
 Suite 1A
 South Portland, ME 04106
 Tel. 207-200-2100

PLAN AND PROFILE - ENDCLIFFE ROAD
 OF:
IVY SUBDIVISION
 ENDCLIFFE ROAD
 KENNEBUNKPORT, MAINE
 FOR:
IVY THREE, LLC
 2 LIVEWELL DRIVE, SUITE 203
 KENNEBUNK, ME 04043

DESIGNED	SAH
DRAWN	STI
CHECKED	SGD
DATE	4/13/2020
SCALE	1" = 20'
PROJECT	10234

SHEET 3 OF 8



10234_PP.dwg, TAB=24x68

STREAM CROSSING NOTES:

- THE FOLLOWING MEASURES MUST BE TAKEN TO PREVENT EROSION OF SOIL OR FILL MATERIAL FROM DISTURBED AREAS INTO THE RESOURCE:
 - STAKED HAY BALES OR SILT FENCE MUST BE PROPERLY INSTALLED BETWEEN THE AREA OF SOIL DISTURBANCE AND THE RESOURCE BEFORE THE ACTIVITY BEGINS;
 - HAY BALES OR SILT FENCE BARRIERS MUST BE MAINTAINED UNTIL THE DISTURBED AREA IS PERMANENTLY STABILIZED;
 - WITHIN 7 CALENDAR DAYS FOLLOWING THE COMPLETION OF ANY SOIL DISTURBANCE, AND PRIOR TO ANY STORM EVENT, MULCH MUST BE SPREAD ON ANY EXPOSED SOILS;
 - ALL DISTURBED SOILS MUST BE PERMANENTLY STABILIZED; AND
 - WITHIN 30 DAYS OF FINAL STABILIZATION OF THE SITE, ANY SILT FENCE MUST BE REMOVED.
- FILL SIDESLOPES IN A STREAM OR FLOODPLAIN WETLAND MUST BE MAINTAINED AT A SLOPE NO SHALLOWER THAN 3 HORIZONTAL TO 1 VERTICAL AND NO STEEPER THAN 1.5 HORIZONTAL TO 1 VERTICAL. FILL SIDESLOPES MUST BE STABILIZED AT THE COMPLETION OF THE ACTIVITY.
- UNCOMPACTED SOILS OR SANDY SOILS THAT ARE SATURATED AT THE TOE OF A SLOPE WILL BE UNSTABLE AT A 1.5 TO 1 SLOPE.
- A BRIDGE OR CULVERT MUST PROVIDE AN OPENING WITH A CROSS-SECTIONAL AREA AT LEAST EQUAL TO 3 TIMES THE CROSS-SECTIONAL AREA OF THE STREAM CHANNEL OR SUFFICIENT IN SIZE TO ACCOMMODATE 25-YEAR FREQUENCY WATER FLOWS.
- ROAD SURFACES MUST BE CONSTRUCTED IN A MANNER TO PREVENT EROSION OF MATERIAL INTO THE RIVER, STREAM OR BROOK.
- SURFACE WATER ON OR ADJACENT TO CROSSING APPROACHES MUST BE DIVERTED THROUGH VEGETATIVE FILTER AREAS AT LEAST 25 FEET LONG TO AVOID SEDIMENTATION OF THE WATERCOURSE. ROADSIDE DITCHES MAY NOT EXTEND TO THE RESOURCE BEING CROSSED.
- A STREAM FORD MUST BE LINED WITH CRUSHED STONE, BLASTED LEDGE, WASHED STONE, GABION BLANKETS OR GEOTEXTILE MATERIAL FOR EROSION CONTROL WHEN THE NATURAL STREAM BED DOES NOT CONSIST OF LEDGE OR ROCK.
- CULVERT CROSSINGS MUST:
 - BE LIMITED TO 75 FEET IN LENGTH. THIS LIMIT MAY NOT BE EXCEEDED WITHIN A HALF-MILE LENGTH OF THE STREAM OR WITHIN THE LENGTH OF STREAM CONTROLLED BY THE APPLICANT, IF LESS;
 - FOLLOW THE ALIGNMENT AND GRADE OF THE EXISTING STREAM CHANNEL WHERE POSSIBLE. ON PERENNIAL STREAMS THE CULVERT'S GRADIENT MAY NOT EXCEED 1%;
 - HAVE THE BOTTOM OF THE ENTIRE CULVERT INSTALLED AT OR BELOW STREAM BED ELEVATION, EXCEPT FOR ADDITIONAL CULVERTS AT THE SAME CROSSING;
 - BE SEATED ON FIRM GROUND, OR ON GEOTEXTILES, LOGS OR OTHER MATERIALS USED TO STABILIZE THE GROUND;
 - BE COVERED BY SOIL TO A MINIMUM DEPTH OF 1 FOOT OR ACCORDING TO THE CULVERT MANUFACTURER'S SPECIFICATIONS, WHICHEVER IS GREATER;
 - HAVE THE SOIL COMPACTED AT LEAST HALFWAY UP THE SIDE OF THE CULVERT; AND
 - HAVE THE INLET AND OUTLET ENDS STABILIZED BY RIPRAP IN ACCORDANCE WITH SECTION 8 SHORELINE STABILIZATION STANDARDS TO AVOID EROSION OF MATERIAL AROUND THE CULVERT.



NOTE: FOR GUIDANCE ON RIPRAP INSTALLATION, CONSULT THE MAINE EROSION AND SEDIMENT CONTROL BMPs, DATED MARCH 2003. THIS HANDBOOK AND OTHER REFERENCES ARE AVAILABLE FROM THE DEP.

- WHEELED OR TRACKED EQUIPMENT MAY NOT OPERATE IN THE WATER. EQUIPMENT OPERATING ON THE SHORE MAY, WHERE NECESSARY, REACH INTO THE WATER WITH A BUCKET OR SIMILAR EXTENSION. EQUIPMENT MAY CROSS STREAMS ON ROCK, GRAVEL OR LEDGE BOTTOM.
- WORK BELOW THE NORMAL HIGH WATER LINE MUST BE DONE DURING PERIODS OF LOW WATER LEVEL OR FLOW.
- IF THE CROSSING INVOLVES TRENCHING OR DISTURBANCE OF SUBSTRATE IN A RIVER, STREAM OR BROOK BETWEEN OCTOBER 2 AND JULY 14, THE ACTIVITY MUST OCCUR DURING THE TIME PERIOD APPROVED BY THE DEP. THE APPROVED TIME PERIOD MAY BE THE TIME PERIOD PROPOSED BY THE APPLICANT OR AN ALTERNATIVE TIME PERIOD APPROVED BY THE DEP. AN ALTERNATIVE TIME PERIOD WILL BE REQUIRED WHERE IT APPEARS AN UNREASONABLE IMPACT ON WATER QUALITY OR FISHERIES MAY RESULT AT THE POINT OF CROSSING OR IMMEDIATELY DOWNSTREAM OF THE CROSSING. THE APPLICANT WILL BE NOTIFIED BY THE DEP WITHIN 14 DAYS IF AN ALTERNATIVE TIME PERIOD OTHER THAN THE ONE PROPOSED BY THE APPLICANT, IS REQUIRED FOR CONSTRUCTING THE CROSSING.
- IF WORK IS PERFORMED IN A RIVER, STREAM OR BROOK THAT IS LESS THAN THREE FEET DEEP AT THE TIME OF THE ACTIVITY AND AT THE LOCATION OF THE ACTIVITY, THE APPLICANT MUST PROVIDE FOR TEMPORARY DIVERSION OF FLOW TO THE OPPOSITE SIDE OF THE CHANNEL WHILE WORK IS IN PROGRESS.
 - DIVERSION MAY BE ACCOMPLISHED BY PLACING SANDBAGS, TIMBERS, SHEET STEEL, CONCRETE BLOCKS, 6-MIL POLYETHYLENE OR GEOTEXTILES FROM THE BANK TO MIDSTREAM ON THE UPSTREAM SIDE OF THE ACTIVITY. NO MORE THAN TWO-THIRDS (2/3) OR 25 FEET OF STREAM WIDTH, WHICHEVER IS LESS, MAY BE DIVERTED AT ONE TIME.
 - ANY MATERIAL USED TO DIVERT WATER FLOW MUST BE COMPLETELY REMOVED UPON COMPLETION OF THE ACTIVITY, AND THE STREAM SUBSTRATE MUST BE RESTORED TO ITS ORIGINAL CONDITION.
 - A PUMP MAY BE OPERATED, WHERE NECESSARY, FOR A TEMPORARY DIVERSION. THE PUMP OUTLET MUST BE LOCATED AND OPERATED SUCH THAT EROSION OR THE DISCHARGE OF SEDIMENT TO THE WATER IS PREVENTED.
- ALL WHEELED OR TRACKED EQUIPMENT THAT MUST TRAVEL OR WORK IN A VEGETATED WETLAND AREA MUST TRAVEL AND WORK ON MATS OR PLATFORMS IN ORDER TO PROTECT WETLAND VEGETATION.
- ALL EXCAVATED MATERIAL MUST BE STOCKPILED EITHER OUTSIDE THE WETLAND OR ON MATS OR PLATFORMS. HAY BALES OR SILT FENCE MUST BE USED, WHERE NECESSARY, TO PREVENT SEDIMENTATION.
- THE USE OF UNTREATED LUMBER IS PREFERRED. LUMBER PRESSURE TREATED WITH CHROMATED COPPER ARSENATE (CCA) MAY BE USED ONLY IF NECESSARY AND ONLY IF USE IS ALLOWED UNDER FEDERAL LAW AND NOT PROHIBITED FROM SALE UNDER 38 M.R.S.A. 1882, AND PROVIDED IT IS CURED ON DRY LAND IN A WAY THAT EXPOSES ALL SURFACES TO THE AIR FOR A PERIOD OF AT LEAST 21 DAYS PRIOR TO CONSTRUCTION. WOOD TREATED WITH CRESOTE OR PENTACHLOROPHENOL MAY NOT BE USED WHERE IT WILL CONTACT WATER.



- NOTES:
- USE FLEXIBLE RUBBER BOOT WITH TWO STAINLESS STEEL BANDS.
 - LOCATION OF CORED HOLE IN MANHOLE SHOULD BE FIELD CHECKED PRIOR TO INSTALLATION TO ENSURE ADEQUATE SEPARATION FROM MANHOLE BARREL JOINT.

FORCE MAIN TERMINUS MANHOLE
NOT TO SCALE



NOT FOR CONSTRUCTION


ISSUED FOR FINAL SUBDIVISION REVIEW	C	SGD	03/30/2021
REVISED BY TOWN AND PUBLIC INPUT	B	SGD	02/02/2021
ISSUED TO PLANNING BOARD FOR MAJOR REVISION REVIEW	A	SGD	10/28/2020
REV. BY:	DATE:	STATUS:	

THIS PLAN SHALL NOT BE MODIFIED WITHOUT WRITTEN PERMISSION FROM SEBAGO TECHNICS, INC. ANY ALTERATIONS, AUTHORIZED OR OTHERWISE, SHALL BE AT THE USER'S SOLE RISK AND WITHOUT LIABILITY TO SEBAGO TECHNICS, INC.



SEBAGO
TECHNICS
WWW.SEAGOTECHNICS.COM
75 John Roberts Rd.
Suite 4A
South Portland, ME 04106
Tel. 207-260-2100

UTILITY CONNECTION PLAN
OF:
IVY SUBDIVISION
ENDCLIFFE ROAD
KENNEBUNKPORT, MAINE
FOR:
IVY THREE, LLC
2 LIVEWELL DRIVE, SUITE 203
KENNEBUNK, ME 04043

DESIGNED	CPT
DRAWN	STI
CHECKED	CPT
DATE	09/03/2020
SCALE	1" = 40'
PROJECT	10234



DRIVEWAY CENTERLINE AND LOT 2B SEWER SERVICE



NOT FOR CONSTRUCTION

REV	BY	DATE	STATUS
C	SGD	03/30/2021	ISSUED FOR FINAL SUBDIVISION REVIEW
B	SGD	02/02/2021	REVISED BY TOWN AND PUBLIC INPUT
A	SGD	10/28/2020	ISSUED TO PLANNING BOARD FOR MAJOR REVISION REVIEW

THIS PLAN SHALL NOT BE MODIFIED WITHOUT WRITTEN PERMISSION FROM SEBAGOTECHNICS, INC. ANY ALTERATIONS, AUTHORIZED OR OTHERWISE, SHALL BE AT THE USER'S SOLE RISK AND WITHOUT LIABILITY TO SEBAGOTECHNICS, INC.

SEBAGO
TECHNICS
www.sebagotechnics.com
75 John Roberts Rd.
South Portland, ME 04106
Tel. 207-200-2100

UTILITY CONNECTION PROFILE
 OF:
 IVY SUBDIVISION
 ENDCLIFFE ROAD
 KENNEBUNKPORT, MAINE
 FOR:
 IVY THREE, LLC
 2 LIVEWELL DRIVE, SUITE 203
 KENNEBUNK, ME 04043

DESIGNED	CPT
DRAWN	STI
CHECKED	CPT
DATE	09/03/2020
SCALE	1" = 40'
PROJECT	10234

10234_U-04mp_TAB PROFILE CHRISTOPHER P. TAYLOR, P.E. 16677 03/30/21

EROSION CONTROL MEASURES

PRE-CONSTRUCTION PHASE

PRIOR TO THE BEGINNING OF ANY CONSTRUCTION, SEDIMENT BARRIERS (SILT FENCE) WILL BE STAKED/INSTALLED ACROSS THE SLOPE(S), ON THE CONTOUR AT OR JUST BELOW THE LIMITS OF CLEARING OR GRUBBING, AND/OR JUST ABOVE ANY ADJACENT PROPERTY LINE OR WATERCOURSE TO PROTECT AGAINST CONSTRUCTION RELATED EROSION. THE PLACEMENT OF SEDIMENT BARRIERS SHALL BE COMPLETED IN ACCORDANCE WITH GUIDELINES ESTABLISHED IN BEST MANAGEMENT PRACTICES AND IN ACCORDANCE WITH THIS EROSION CONTROL PLAN AND DETAILS IN THIS PLAN SET. THIS NETWORK IS TO BE MAINTAINED BY THE CONTRACTOR UNTIL ALL EXPOSED SLOPES HAVE AT LEAST 90% VIGOROUS PERENNIAL VEGETATIVE COVER TO PREVENT EROSION. TEMPORARY EROSION CONTROL MEASURES SHALL BE REMOVED WITHIN 30 DAYS AFTER PERMANENT STABILIZATION IS ATTAINED.

PRIOR TO ANY CLEARING OR GRUBBING, A CONSTRUCTION ENTRANCE/EXIT SHALL BE CONSTRUCTED AT THE INTERSECTION OF THE PROPOSED ENTRANCES AND EXISTING ROADWAY TO AVOID TRACKING OF MUD, DUST AND DEBRIS FROM THE SITE.

PRIOR TO CONSTRUCTION, THE CONTRACTOR SHALL PREPARE A DETAILED SCHEDULE AND MARKED UP PLAN INDICATING AREAS AND COMPONENTS OF THE WORK AND KEY DATES SHOWING DATE OF DISTURBANCE AND COMPLETION OF THE WORK. THE CONTRACTOR SHALL SCHEDULE A PRE-CONSTRUCTION MEETING WITH THE MUNICIPAL STAFF. THREE COPIES OF THE SCHEDULE AND MARKED UP PLAN SHALL BE PROVIDED TO THE MUNICIPALITY THREE DAYS PRIOR TO THE SCHEDULED PRE-CONSTRUCTION MEETING. SPECIAL ATTENTION SHALL BE GIVEN TO THE 14 DAY LIMIT OF DISTURBANCE IN THE SCHEDULE ADDRESSING TEMPORARY AND PERMANENT VEGETATION MEASURES.

CONSTRUCTION AND POST-CONSTRUCTION PHASE

AREAS UNDERGOING ACTUAL CONSTRUCTION SHALL ONLY EXPOSE THAT AMOUNT OF MINERAL SOIL NECESSARY FOR PROGRESSIVE AND EFFICIENT CONSTRUCTION. AN AREA CONSIDERED OPEN IS ANY AREA NOT STABILIZED WITH PAVEMENT, VEGETATION, MULCHING, EROSION CONTROL MATS, RIPRAP OR GRAVEL BASE ON A ROAD, SUCH AS ACTIVE EXCAVATION AND ACTIVE GRADING. LIMIT THE EXPOSED AREA TO THOSE AREAS IN WHICH WORK IS ACTIVELY OCCURRING OR CAN BE MULCHED IN THE SAME DAY. OPEN AREAS SHALL BE ANCHORED WITH TEMPORARY EROSION CONTROL, AS SHOWN ON THE DESIGN PLANS AND AS DESCRIBED WITHIN THIS EROSION CONTROL PLAN WITHIN SEVEN (7) DAYS OF DISTURBANCE. AREAS LOCATED WITHIN 100 FEET OF STREAMS SHALL BE ANCHORED WITH TEMPORARY EROSION CONTROL WITHIN SEVEN (7) DAYS. REFER TO WINTER EROSION CONTROL NOTES FOR THE TREATMENT OF OPEN AREAS AFTER OCTOBER 1ST OF THE CONSTRUCTION YEAR.

THE CONTRACTOR MUST INSTALL ANY ADDED MEASURES WHICH MAY BE NECESSARY TO CONTROL EROSION/SEDIMENTATION FROM THE SITE DEPENDENT UPON THE ACTUAL SITE AND WEATHER CONDITIONS. CONTINUATION OF EARTHWORK OPERATIONS ON ADDITIONAL AREAS SHALL NOT BEGIN UNTIL THE EXPOSED SOIL SURFACE ON THE AREA BEING WORKED HAS BEEN STABILIZED, IN ORDER TO MINIMIZE AREAS WITHOUT EROSION CONTROL PROTECTION.

EROSION CONTROL APPLICATIONS & MEASURES

THE PLACEMENT OF EROSION CONTROL MEASURES SHALL BE COMPLETED IN ACCORDANCE WITH GUIDELINES ESTABLISHED IN BEST MANAGEMENT PRACTICES AND IN ACCORDANCE WITH THE EROSION CONTROL PLAN AND DETAILS IN THE PLAN SET.

1. TEMPORARY MULCHING:

ALL DISTURBED AREAS SHALL BE MULCHED WITH MATERIALS SPECIFIED BELOW PRIOR TO ANY STORM EVENT. ALL DISTURBED AREAS NOT FINAL GRADED WITHIN 14 DAYS SHALL BE MULCHED. DISTURBED AREAS ADJACENT TO NATURAL RESOURCES THAT ARE NOT GRADED WITHIN SEVEN (7) DAYS SHALL BE MULCHED. ALSO, AREAS WHICH HAVE BEEN TEMPORARILY OR PERMANENTLY SEEDED, SHALL BE MULCHED IMMEDIATELY FOLLOWING SEEDING. EROSION CONTROL BLANKETS ARE RECOMMENDED TO BE USED AT THE BASE OF MEETING WATERWAYS AND ON SLOPES GREATER THAN 33%. MULCH ANCHORING SHOULD BE USED ON SLOPES GREATER THAN 5% AFTER SEPTEMBER 15TH OF THE CONSTRUCTION YEAR (SEE WINTER EROSION CONTROL NOTES).
TYPES OF MULCH:

HAY OR STRAW SHALL BE APPLIED AT A RATE OF 75 LBS/1,000 S.F. (1.5 TONS PER ACRE).

EROSION CONTROL MIX SHALL BE PLACED EVENLY AND MUST PROVIDE 100% SOIL COVERAGE. EROSION CONTROL MIX SHALL BE APPLIED SUCH THAT THE THICKNESS ON SLOPES 3:1 OR LESS IS 2 INCHES PLUS 1/2 INCH PER 20 FEET OF SLOPE UP TO 100 FEET. THE THICKNESS ON SLOPES BETWEEN 3:1 AND 2:1 SHALL BE 4 INCHES PLUS 1/2 INCH PER 20 FEET OF SLOPE UP TO 100 FEET. THIS SHALL NOT BE USED ON SLOPES GREATER THAN 2:1.

EROSION CONTROL BLANKET SHALL BE INSTALLED SUCH THAT CONTINUOUS CONTACT BETWEEN THE MAT AND THE SOIL IS OBTAINED. INSTALL BLANKETS AND STAPLE IN ACCORDANCE WITH THE MANUFACTURER'S RECOMMENDATIONS.

2. SOIL STOCKPILES:

STOCKPILES OF SOIL OR SUBSOIL SHALL BE MULCHED WITH HAY OR STRAW AT A RATE OF 75 LBS/1,000 S.F. (1.5 TONS PER ACRE) OR WITH A FOUR-INCH LAYER OF WOOD WASTE EROSION CONTROL MIX. THIS WILL BE DONE WITHIN 24 HOURS OF STOCKING AND RE-ESTABLISHED PRIOR TO ANY RAINFALL. ANY SOIL STOCKPILE WILL NOT BE REPAIRED (EVEN IF A NATURAL RESOURCE IS ADJACENT) UNTIL IT IS STABILIZED. SEDIMENT BARRIERS SHALL BE INSTALLED DOWNGRADIENT OF STOCKPILES, AND STORMWATER SHALL BE PREVENTED FROM RUNNING INTO THE STOCKPILE.

3. NATURAL RESOURCES PROTECTION:

ANY AREAS WITHIN 100 FEET FROM ANY NATURAL RESOURCES SHALL BE MULCHED USING TEMPORARY MULCHING (AS DESCRIBED IN PART 1 OF THIS SECTION) WITHIN 7 DAYS OF EXPOSURE OR PRIOR TO ANY STORM EVENT. SEDIMENT BARRIERS (AS DESCRIBED IN PART 4 OF THIS SECTION) SHALL BE PLACED BETWEEN ANY NATURAL RESOURCE AND THE DISTURBED AREA. PROJECTS CROSSING THE NATURAL RESOURCE SHALL BE PROTECTED A MINIMUM DISTANCE OF 100 FEET ON EITHER SIDE FROM THE RESOURCE.

4. SEDIMENT BARRIERS:

PRIOR TO THE BEGINNING OF ANY CONSTRUCTION, SEDIMENT BARRIERS SHALL BE STAKED ACROSS THE SLOPE(S), ON THE CONTOUR AT OR JUST BELOW THE LIMITS OF CLEARING OR GRUBBING, AND/OR JUST ABOVE ANY ADJACENT PROPERTY LINE OR WATERCOURSE TO PROTECT AGAINST CONSTRUCTION RELATED EROSION. SEDIMENT BARRIERS SHALL BE MAINTAINED BY THE CONTRACTOR UNTIL ALL EXPOSED SLOPES HAVE AT LEAST 90% VIGOROUS PERENNIAL VEGETATIVE COVER TO PREVENT EROSION.

SILT FENCE SHALL BE INSTALLED PER THE DETAIL ON THE PLANS. THE EFFECTIVE HEIGHT OF THE FENCE SHALL NOT EXCEED 36 INCHES. IT IS RECOMMENDED THAT SILT FENCE BE REMOVED BY CUTTING THE ADJACENT MATERIALS AT GROUND LEVEL SO AS TO AVOID ADDITIONAL SOIL DISTURBANCE.

HAY BALES SHALL NOT BE INSTALLED ADJACENT TO WETLAND. INSTALL PER THE DETAIL ON THE PLANS. BALES SHALL BE WIRE-BOUND OR STRING-TIED AND THESE BINDINGS MUST REMAIN PARALLEL WITH THE GROUND SURFACE DURING INSTALLATION TO PREVENT DETERIORATION OF THE BINDINGS. BALES SHALL BE INSTALLED WITHIN A MINIMUM 4 INCH DEEP TRENCH LINE WITH ENDS OF ADJACENT BALES TIGHTLY ABUTTING ONE ANOTHER.

EROSION CONTROL MIX SHALL NOT BE USED ADJACENT TO WETLANDS. INSTALL PER THE DETAIL ON THE PLANS. THE MIX SHALL CONSIST PRIMARILY OF ORGANIC MATERIAL AND CONTAIN NO WELL-SORTED ROCKS LESS THAN 4 INCH IN DIAMETER. THE MIX COMPOSITION SHALL MEET THE STANDARDS DESCRIBED WITHIN THE MDEP BEST MANAGEMENT PRACTICES. NO TRENCHING IS REQUIRED FOR INSTALLATION OF THIS BARRIER. EROSION CONTROL MIX BERMS SHALL NOT BE USED AT THE BOTTOM OF STEEP SLOPES (>8%) OR SLOPES WITH FLOWING WATER.

CONTINUOUS CONTAINED BERM SHALL BE INSTALLED PER THE DETAIL ON THE PLANS. THIS SEDIMENT BARRIER IS EROSION CONTROL MIX PLACED WITH A SYNTHETIC TUBULAR NETTING AND PERFORMS AS A STURDY SEDIMENT BARRIER THAT WORKS WELL ON HARD GROUND SUCH AS FROZEN CONDITIONS, TRAVELED AREAS OR PAVEMENT. NO TRENCHING IS REQUIRED FOR INSTALLATION OF THIS BARRIER.

5. TEMPORARY CHECK DAMS:

SHALL BE INSTALLED PER THE DETAIL ON THE PLANS. CHECK DAMS ARE TO BE PLACED WITHIN DITCHES/ SWALES AS SPECIFIED ON THE DESIGN PLANS IMMEDIATELY AFTER FINAL GRADING. CHECK DAMS SHALL BE 2 FEET HIGH. TEMPORARY CHECK DAMS MAY BE REMOVED ONLY AFTER THE ROADWAYS ARE PAVED AND THE VEGETATED SWALE ARE ESTABLISHED WITH AT LEAST 90% OF VIGOROUS PERENNIAL GROWTH. THE AREA BENEATH THE CHECK DAM MUST BE SEEDED AND MULCHED IMMEDIATELY AFTER REMOVAL OF THE CHECK DAM.

STONE CHECK DAMS: STONE DAMS SHOULD BE CONSTRUCTED OF 2 TO 3 INCH STONE AND PLACED SUCH THAT COMPLETE COVERAGE OF THE SWALE IS OBTAINED AND THAT THE CENTER OF THE DAM IS 6 INCHES LOWER THAN THE OUTER EDGES.

HAY BALE CHECK DAMS: BALES SHALL BE WIRE-BOUND OR STRING-TIED. BALES SHALL BE INSTALLED WITHIN A MINIMUM 4 INCH DEEP TRENCH LINE WITH ENDS OF ADJACENT BALES TIGHTLY ABUTTING ONE ANOTHER. HAY BALES SHALL BE PLACED SUCH THAT COMPLETE COVERAGE OF THE SWALE IS OBTAINED AND THAT THE CENTER OF THE DAM IS 6 INCHES LOWER THAN THE OUTER EDGES.

MANUFACTURED CHECK DAMS: MANUFACTURED CHECK DAMS, AS SPECIFIED IN THE DETAIL ON THE PLANS, MAY BE USED IF AUTHORIZED BY THE PROPER LOCAL, STATE OR FEDERAL REGULATING AGENCIES. THESE UNITS SHALL BE INSTALLED IN ACCORDANCE WITH THE MANUFACTURER'S RECOMMENDATIONS.

6. STORMDRAIN INLET PROTECTION:

INLET PROTECTION SHALL BE PLACED AROUND A STORMDRAIN DROP INLET OR CURB INLET PRIOR TO PERMANENT STABILIZATION OF THE IMMEDIATE AND UPSTREAM DISTURBED AREAS. THEY SHALL BE CONSTRUCTED IN A MANNER THAT WILL FACILITATE CLEAN-OUT AND DISPOSAL OF TRAPPED SEDIMENTS AND MINIMIZE INTERFERENCE WITH CONSTRUCTION ACTIVITIES. ANY RESULTANT PONDING OF WATER FROM THE PROTECTION METHOD MUST NOT CAUSE EXCESSIVE INCONVENIENCE OR DAMAGE TO ADJACENT AREAS OR STRUCTURES.

HAY BALE DROP INLET PROTECTION: WE DO NOT RECOMMEND THE USE OF HAY BALES AS INLET PROTECTION.

CONCRETE BLOCK AND STONE INLET SEDIMENT FILTER (DROP OR CURB INLET): SHALL BE INSTALLED PER THE DETAIL ON THE PLANS. THE HEIGHT OF THE CONCRETE BLOCK BARRIER CAN VARY BUT MUST BE BETWEEN 12 AND 24 INCHES TALL. A MINIMUM OF 1 INCH CRUSHED STONE SHALL BE USED.

MANUFACTURED SEDIMENT BARRIERS AND FILTER (DROP OR CURB INLET): MANUFACTURED FILTERS, AS SPECIFIED IN THE DETAIL ON THE PLANS, MAY BE USED IF INSTALLED IN ACCORDANCE WITH THE MANUFACTURER'S RECOMMENDATIONS.

7. STABILIZED CONSTRUCTION ENTRANCE/EXIT:

PRIOR TO CLEARING AND/OR GRUBBING THE SITE A STABILIZED CONSTRUCTION ENTRANCE/EXIT SHALL BE CONSTRUCTED WHEREVER TRAFFIC WILL EXIT THE CONSTRUCTION SITE ONTO A PAVED ROADWAY IN ORDER TO MINIMIZE THE TRACKING OF SEDIMENT AND DEBRIS FROM THE CONSTRUCTION SITE ONTO PUBLIC ROADWAYS. THE ENTRANCES AND ADJACENT ROADWAY AREAS SHALL BE PERIODICALLY SWEEPED TO FURTHER MINIMIZE THE TRACKING OF MUD, DUST OR DEBRIS FROM THE CONSTRUCTION AREA. THE TERM "SWEEP" IS UNDERSTOOD TO MEAN REMOVAL AND RECOVERY OF TRACKED SEDIMENT WITH A STREET SWEEPER, NOT BRUSHING THE MATERIAL INTO SWALES OR STRUCTURES WITH A MECHANICAL BROOM. STABILIZED CONSTRUCTION EXITS SHALL BE CONSTRUCTED IN AREAS SPECIFIED ON THE PLANS AND AS DETAILED ON THE PLANS. THE CONTRACTOR SHALL MAINTAIN THE STABILIZED CONSTRUCTION ENTRANCE UNTIL ALL DISTURBED AREAS ARE STABILIZED.

DUST CONTROL:

DUST CONTROL DURING CONSTRUCTION SHALL BE ACHIEVED BY THE USE OF A WATERING TRUCK TO PERIODICALLY SPRINKLE THE EXPOSED ROADWAY AREAS AS NECESSARY TO REDUCE DUST DURING THE DRY MONTHS. APPLYING OTHER DUST CONTROL PRODUCTS SUCH AS CALCIUM CHLORIDE OR OTHER MANUFACTURED PRODUCTS ARE ALLOWED IF AUTHORIZED BY THE PROPER LOCAL, STATE AND/OR FEDERAL REGULATING AGENCIES. HOWEVER, IT IS THE CONTRACTOR'S ULTIMATE RESPONSIBILITY TO MITIGATE DUST AND SOIL LOSS FROM THE SITE. IF OFFSITE TRACKING OCCURS, PUBLIC ROADS SHOULD BE SWEEPED IMMEDIATELY AND NOT LESS THAN ONCE A WEEK AND PRIOR TO SIGNIFICANT STORM EVENTS.

TEMPORARY VEGETATION:

TEMPORARY VEGETATION SHALL BE APPLIED TO DISTURBED AREAS THAT WILL NOT RECEIVE FINAL GRADING FOR PERIODS UP TO 12 MONTHS. THIS PROCEDURE SHOULD BE USED EXTENSIVELY IN AREAS ADJACENT TO NATURAL RESOURCES. SEEDBED PREPARATION AND APPLICATION OF SEED SHALL BE CONDUCTED AS INDICATED IN THE PERMANENT VEGETATION SECTION OF THIS NARRATIVE. SPECIFIC SEEDS (FAST GROWING AND SHORT LIVING) SHALL BE SELECTED FROM THE MAINE EROSION AND SEDIMENT CONTROL BMP MANUALS FOR CONTRACTORS AND ENGINEERS, 2016 OR LATEST REVISION. ALTERNATIVE EROSION CONTROL MEASURES SHOULD BE USED IF SEEDING CAN NOT BE DONE BEFORE SEPTEMBER 15TH OF THE CONSTRUCTION YEAR.

PERMANENT VEGETATION:

REVEGETATION MEASURES SHALL COMMENCE IMMEDIATELY UPON COMPLETION OF FINAL GRADING OF AREAS TO BE LOAMED AND SEEDED. THE APPLICATION OF SEED SHALL BE CONDUCTED BETWEEN APRIL 1ST AND OCTOBER 1ST OF THE CONSTRUCTION YEAR, PLEASE REFER TO THE WINTER EROSION CONTROL NOTES FOR MORE DETAIL. REVEGETATION MEASURES SHALL CONSIST OF THE FOLLOWING:

SEEDBED PREPARATION:

- A. FOUR (4) INCHES OF LOAM SHALL BE SPREAD OVER DISTURBED AREAS AND SMOOTHED TO A UNIFORM SURFACE. LOAM SHALL BE FREE OF SUBSOL, CLAY LUMPS, STONES AND OTHER OBJECTS OVER 2 INCHES OR LARGER IN ANY DIMENSION, AND WITHOUT WEEDS, ROOTS OR OTHER OBJECTIONABLE MATERIAL.
- B. SOILS TESTS SHALL BE TAKEN AT THE TIME OF SOIL STRIPPING TO DETERMINE FERTILIZATION REQUIREMENTS. SOILS TESTS SHALL BE TAKEN PROMPTLY AS TO NOT INTERFERE WITH CONSTRUCTION. SOILS TESTS SHALL BE BASED UPON TEST RESULTS. SOIL AMENDMENTS SHALL BE INCORPORATED INTO THE SOIL PRIOR TO FINAL SEEDING. IN LIEU OF SOIL TESTS, SOIL AMENDMENTS MAY BE APPLIED AS FOLLOWS:

ITEM	APPLICATION RATE
10-20-20 FERTILIZER (N-P205-K20 OR EQUAL)	18.4 LBS./1,000 S.F.
GROUND LIMESTONE (50% CALCIUM & MAGNESIUM OXIDE)	138 LBS./1,000 S.F.

- C. WORK LIME AND FERTILIZER INTO THE SOIL AS NEARLY AS PRACTICAL TO A DEPTH OF 4 INCHES WITH PROPER EQUIPMENT. ROLL THE AREA TO FIRM THE SEEDED EXCEPT ON CLAY OR SILTY SOILS OR COARSE SAND.

APPLICATION OF SEED:

- A. SEEDING SHALL BE CONDUCTED BETWEEN APRIL 1ST AND OCTOBER 1ST OF THE CONSTRUCTION YEAR. GENERALLY A SEED MIXTURE MAY BE APPLIED AS FOLLOWS: (MDEP SEED MIX 2 IS DISPLAYED)

SEED TYPE	APPLICATION RATE
CREeping RED FESCUE	0.46 LBS/1,000 S.F. (20 LBS/ACRE)
REEDTOP	0.05 LBS/1,000 S.F. (2 LBS/ACRE)
TALL FESCUE	0.46 LBS/1,000 S.F. (20 LBS/ACRE)
TOTAL:	0.97 LBS/1,000 S.F. (42 LBS/ACRE)

NOTE: A SPECIFIC SEED MIXTURE SHOULD BE CHOSEN TO MATCH THE SOILS CONDITION OF THE SITE. VARIOUS AGENCIES CAN RECOMMEND SEED MIXTURES. MDEP RECOMMENDED SEED MIXTURES ARE IN THE EROSION AND SEDIMENT CONTROL BMP MANUAL DATED 2016 OR LATEST REVISION.

- B. HYDROSEEDING: SHALL BE CONDUCTED ON PREPARED AREAS WITH SLOPES LESS THAN 2:1. LIME AND FERTILIZER MAY BE APPLIED SIMULTANEOUSLY WITH THE SEED. RECOMMENDED SEEDING RATES MUST BE INCREASED BY 10% WHEN HYDROSEEDING.

- C. MULCHING: SHALL COMMENCE IMMEDIATELY AFTER SEED IS APPLIED. REFER TO THE TEMPORARY MULCHING SECTION OF THIS NARRATIVE FOR DETAILS.

SODDING:

FOLLOWING SEEDED PREPARATION, SOD CAN BE APPLIED IN LIEU OF SEEDING IN AREAS WHERE IMMEDIATE VEGETATION IS MOST BENEFICIAL, SUCH AS DITCHES, AROUND STORMWATER DROP INLETS AND AREAS OF AESTHETIC VALUE. SOD SHOULD BE LAID AT RIGHT ANGLES TO THE DIRECTION OF FLOW, STARTING AT THE LOWEST ELEVATION. SOD SHOULD BE ROLLED OR TAMPED DOWN TO EVEN OUT THE JOINTS ONCE LAID DOWN, WHERE FLOW IS PREVALENT THE SOD MUST BE PROPERLY ANCHORED DOWN. IRRIGATE THE SOD IMMEDIATELY AFTER INSTALLATION. IN MOST CASES, SOD CAN BE ESTABLISHED BETWEEN APRIL 1ST AND NOVEMBER 15TH OF THE CONSTRUCTION YEAR, HOWEVER, REFER TO THE WINTER EROSION CONTROL NOTES FOR ANY ACTIVITIES AFTER OCTOBER 1ST.

STANDARDS FOR TIMELY STABILIZATION:

STANDARD FOR THE TIMELY STABILIZATION OF DISTURBED SLOPES -- THE CONTRACTOR WILL CONSTRUCT AND STABILIZE STONE-COVERED SLOPES BY NOVEMBER 15. THE CONTRACTOR WILL SEED AND MULCH ALL SLOPES TO BE VEGETATED BY SEPTEMBER 15. THE MDEP WILL CONSIDER ANY AREA HAVING A GRADE GREATER THAN 15% (10H:1V) TO BE A SLOPE. IF THE CONTRACTOR FAILS TO STABILIZE ANY SLOPE TO BE VEGETATED BY SEPTEMBER 15, THEN THE CONTRACTOR WILL TAKE ONE OF THE FOLLOWING ACTIONS TO STABILIZE THE SLOPE FOR LATE FALL AND WINTER:

- A. STABILIZE THE SOIL WITH TEMPORARY VEGETATION AND EROSION CONTROL MATS -- BY OCTOBER 1 THE CONTRACTOR WILL SEED THE DISTURBED SLOPE WITH WINTER RYE AT A SEEDING RATE OF 3 POUNDS PER 1,000 SQUARE FEET AND APPLY EROSION CONTROL MATS OVER THE MULCHED SLOPE. THE CONTRACTOR WILL MONITOR GROWTH OF THE RYE OVER THE NEXT 30 DAYS. IF THE RYE FAILS TO GROW AT LEAST THREE INCHES OR COVER AT LEAST 75% OF THE DISTURBED SLOPE BY NOVEMBER 1, THEN THE APPLICANT WILL COVER THE SLOPE WITH A LAYER OF WOOD WASTE COMPOST AS DESCRIBED IN ITEM 2(C); OF THIS STANDARD OR WITH STONE RIPRAP AS DESCRIBED IN ITEM 2(D), OF THIS STANDARD.
- B. STABILIZE THE SLOPE WITH SOD -- THE CONTRACTOR WILL STABILIZE THE DISTURBED SLOPE WITH PROPERLY INSTALLED SOD BY OCTOBER 1. PROPER INSTALLATION INCLUDES THE APPLICANT FINNING THE SOD ONTO THE SLOPE WITH WIRE PINS, ROLLING THE SOD TO GUARANTEE CONTACT BETWEEN THE SOD AND UNDERLYING SOIL, AND WATERING THE SOD TO PROMOTE ROOT GROWTH INTO THE DISTURBED SOIL. THE APPLICANT WILL NOT USE LATE-SEASON SOD INSTALLATION TO STABILIZE SLOPES HAVING A GRADE GREATER THAN 33% (3H:1V).
- C. STABILIZE THE SLOPE WITH WOOD WASTE COMPOST -- THE CONTRACTOR WILL PLACE A SIX-INCH LAYER OF WOOD WASTE COMPOST ON THE SLOPE BY NOVEMBER 15. PRIOR TO PLACING THE WOOD WASTE COMPOST, THE APPLICANT WILL REMOVE ANY SNOW ACCUMULATION ON THE DISTURBED SLOPE. THE APPLICANT WILL NOT USE WOOD WASTE COMPOST TO STABILIZE SLOPES HAVING GRADES GREATER THAN 50% (2H:1V) OR HAVING GROUNDWATER SEEPS ON THE SLOPE FACE.
- D. STABILIZE THE SLOPE WITH STONE RIPRAP -- THE CONTRACTOR WILL PLACE A LAYER OF STONE RIPRAP ON THE SLOPE BY NOVEMBER 15. THE APPLICANT WILL HIRE A REGISTERED PROFESSIONAL ENGINEER TO DETERMINE THE STONE SIZE NEEDED FOR STABILITY AND TO DESIGN A FILTER LAYER FOR UNDERNEATH THE RIPRAP.

STANDARD FOR THE TIMELY STABILIZATION OF DISTURBED SOILS -- BY SEPTEMBER 15 THE CONTRACTOR WILL SEED AND MULCH ALL DISTURBED SOILS ON AREAS HAVING A SLOPE LESS THAN 15%. IF THE CONTRACTOR FAILS TO STABILIZE THESE SOILS BY THIS DATE, THEN THE CONTRACTOR WILL TAKE ONE OF THE FOLLOWING ACTIONS TO STABILIZE THE SOIL FOR LATE FALL AND WINTER:

- A. STABILIZE THE SOIL WITH TEMPORARY VEGETATION -- BY OCTOBER 1 THE CONTRACTOR WILL SEED THE DISTURBED SOIL WITH WINTER RYE AT A SEEDING RATE OF 3 POUNDS PER 1000 SQUARE FEET. LIGHTLY MULCH THE SEEDED SOIL WITH HAY OR STRAW AT 75 POUNDS PER 1000 SQUARE FEET, AND ANCHOR THE MULCH WITH PLASTIC NETTING. THE APPLICANT WILL MONITOR GROWTH OF THE RYE OVER THE NEXT 30 DAYS. IF THE RYE FAILS TO GROW AT LEAST THREE INCHES OR COVER AT LEAST 75% OF THE DISTURBED SOIL BEFORE NOVEMBER 15, THEN THE APPLICANT WILL MULCH THE AREA FOR OVER-WINTER PROTECTION AS DESCRIBED IN ITEM 3(C) OF THIS STANDARD.
- B. STABILIZE THE SOIL WITH SOD -- THE APPLICANT WILL STABILIZE THE DISTURBED SOIL WITH PROPERLY INSTALLED SOD BY OCTOBER 1. PROPER INSTALLATION INCLUDES THE APPLICANT FINNING THE SOD ONTO THE SOIL WITH WIRE PINS, ROLLING THE SOD TO GUARANTEE CONTACT BETWEEN THE SOD AND UNDERLYING SOIL, AND WATERING THE SOD TO PROMOTE ROOT GROWTH INTO THE DISTURBED SOIL.
- C. STABILIZE THE SOIL WITH MULCH -- BY NOVEMBER 15 THE APPLICANT WILL MULCH THE DISTURBED SOIL BY SPREADING HAY OR STRAW AT A RATE OF AT LEAST 150 POUNDS PER 1000 SQUARE FEET ON THE AREA SO THAT NO SOIL IS VISIBLE THROUGH THE MULCH. PRIOR TO APPLYING THE MULCH, THE APPLICANT WILL REMOVE ANY SNOW ACCUMULATION ON THE DISTURBED AREA. IMMEDIATELY AFTER APPLYING THE MULCH, THE APPLICANT WILL ANCHOR THE MULCH WITH PLASTIC NETTING TO PREVENT WIND FROM MOVING THE MULCH OFF THE DISTURBED SOIL.

- 1. MAINTENANCE MEASURES SHALL BE APPLIED AS NEEDED DURING THE ENTIRE CONSTRUCTION CYCLE. AFTER EACH RAINFALL, SNOW STORM OR PERIOD OF THAWING AND RUNOFF, THE CONTRACTOR SHALL PERFORM A VISUAL INSPECTION OF ALL INSTALLED EROSION CONTROL MEASURES. THE CONTRACTOR SHALL PERFORM REPAIRS NO LATER THAN THE END OF THE NEXT WORKDAY, TO ALLOW CONTINUED PROPER FUNCTIONING OF THE EROSION CONTROL MEASURE. THE CONTRACTOR SHALL PROVIDE THE NECESSARY REGULATING AGENCIES WITH WRITTEN DOCUMENTATION DESCRIBING DATES OF INSPECTIONS AND NECESSARY FOLLOW-UP WORK TO MAINTAIN EROSION CONTROL MEASURES MEETING THE REQUIREMENTS OF THIS PLAN WITHIN SEVEN (7) DAYS.
- 2. FOLLOWING THE TEMPORARY AND/OR FINAL SEEDINGS, THE CONTRACTOR SHALL INSPECT THE WORK AREA SEMI-MONTHLY UNTIL THE SEEDINGS HAVE BEEN ESTABLISHED. ESTABLISHED MEANS A MINIMUM OF 90% OF AREAS VEGETATED WITH VIGOROUS GROWTH. RESEEDING SHALL BE CARRIED OUT BY THE CONTRACTOR WITH FOLLOW-UP INSPECTIONS IN THE EVENT OF ANY FAILURES UNTIL VEGETATION IS ADEQUATELY ESTABLISHED.

HOUSEKEEPING:

- 1. SPILL PREVENTION: CONTROLS MUST BE USED TO PREVENT POLLUTANTS FROM CONSTRUCTION AND WASTE MATERIALS STORED ON SITE TO ENTER STORMWATER, WHICH INCLUDES STORAGE PRACTICES TO MINIMIZE EXPOSURE OF THE MATERIALS TO STORMWATER. THE SITE CONTRACTOR OR OPERATOR MUST DEVELOP, AND IMPLEMENT AS NECESSARY, APPROPRIATE SPILL PREVENTION, CONTAINMENT, AND RESPONSE PLANNING MEASURES.
- 2. GROUNDWATER PROTECTION: DURING CONSTRUCTION, LIQUID PETROLEUM PRODUCTS AND OTHER HAZARDOUS MATERIALS WITH THE POTENTIAL TO CONTAMINATE GROUNDWATER MAY NOT BE STORED OR HANDLED IN AREAS OF THE SITE DRAINING TO AN INFILTRATION AREA. AN "INFILTRATION AREA" IS ANY AREA OF THE SITE THAT BY DESIGN OR AS A RESULT OF SOILS, TOPOGRAPHY AND OTHER RELEVANT FACTORS ACCUMULATES RUNOFF THAT INFILTRATES INTO THE SOIL, DIKES, BERMS, SUMPS, AND OTHER FORMS OF SECONDARY CONTAINMENT THAT PREVENT DISCHARGE TO GROUNDWATER MAY BE USED TO INSULATE PORTIONS OF THE SITE FOR THE PURPOSES OF STOPPING AND REDUCING INFILTRATION OF STORED MATERIALS. ANY PROJECT PROPOSING INFILTRATION OF STORED MATERIALS MUST PROVIDE ADEQUATE PRE-TREATMENT OF STORMWATER PRIOR TO DISCHARGE OF STORMWATER TO THE INFILTRATION AREA, OR PROVIDE FOR TREATMENT WITHIN THE INFILTRATION AREA, IN ORDER TO PREVENT THE ACCUMULATION OF FINES, REDUCTION IN INFILTRATION RATE, AND CONSEQUENT FLOODING AND DESTABILIZATION.
- 3. FUGITIVE SEDIMENT AND DUST: ACTIONS MUST BE TAKEN TO ENSURE THAT ACTIVITIES DO NOT RESULT IN NOTICEABLE EROSION OF SOILS OR FUGITIVE DUST EMISSIONS DURING OR AFTER CONSTRUCTION. OIL MAY NOT BE USED FOR DUST CONTROL, BUT OTHER WATER ADDITIVES MAY BE CONSIDERED AS NEEDED. A STABILIZED CONSTRUCTION ENTRANCE (SCE) SHOULD BE INCLUDED TO MINIMIZE TRACKING OF MUD AND SEDIMENT. IF OFF-SITE TRACKING OCCURS, PUBLIC ROADS SHOULD BE SWEEP IMMEDIATELY AND NO LESS THAN ONCE A WEEK AND PRIOR TO SIGNIFICANT STORM EVENTS. OPERATIONS DURING DRY MONTHS, THAT EXPERIENCE FUGITIVE DUST PROBLEMS, SHOULD WET DOWN UNPAVED ACCESS ROADS ONCE A WEEK OR MORE FREQUENTLY AS NEEDED WITH A WATER ADDITIVE TO SUPPRESS FUGITIVE SEDIMENT AND DUST.
- 4. DEBRIS AND OTHER MATERIALS: MINIMIZE THE EXPOSURE OF CONSTRUCTION DEBRIS, BUILDING AND LANDSCAPING MATERIALS, TRASH, FERTILIZERS, PESTICIDES, HERBICIDES, DETERGENTS, SANITARY WASTE AND OTHER MATERIALS TO PRECIPITATION AND STORMWATER RUNOFF. THESE MATERIALS MUST BE PREVENTED FROM BECOMING A POLLUTANT SOURCE.
- 5. EXCAVATION DE-WATERING: EXCAVATION DE-WATERING IS THE REMOVAL OF WATER FROM TRENCHES, FOUNDATIONS, COFFER DAMS, PONDS, AND OTHER AREAS WITHIN THE CONSTRUCTION AREA THAT RETAIN WATER AFTER EXCAVATION. IN MOST CASES THE COLLECTED WATER IS HEAVILY SILTED AND HINDERS CORRECT AND SAFE CONSTRUCTION PRACTICES. THE COLLECTED WATER REMOVED FROM THE PONDED AREA, EITHER THROUGH GRAVITY OR PUMPING, MUST BE SPREAD THROUGH NATURAL WOODED BUFFERS OR REMOVED TO AREAS THAT ARE SPECIFICALLY DESIGNED TO COLLECT THE MAXIMUM AMOUNT OF SEDIMENT POSSIBLE, LIKE A COFFERDAM SEDIMENTATION BASIN. AVOID ALLOWING THE WATER TO FLOW OVER DISTURBED AREAS OF THE SITE. EQUIVALENT MEASURES MAY BE TAKEN IF APPROVED BY THE DEPARTMENT.
- 6. AUTHORIZED NON-STORMWATER DISCHARGES: IDENTIFY AND PREVENT CONTAMINATION BY NON-STORMWATER DISCHARGES, WHERE ALLOWED NON-STORMWATER DISCHARGES EXIST. THEY MUST BE IDENTIFIED AND STEPS SHOULD BE TAKEN TO ENSURE THE IMPLEMENTATION OF APPROPRIATE POLLUTION PREVENTION MEASURES FOR THE NON-STORMWATER COMPONENT(S) OF THE DISCHARGE. AUTHORIZED NON-STORMWATER DISCHARGES ARE:
 - A. DISCHARGES FROM FIRE FIGHTING ACTIVITY;
 - B. FIRE HYDRANT FLUSHINGS;
 - C. VEHICLE WASH-WATER IF DETERGENTS ARE NOT USED AND WASHING IS LIMITED TO THE EXTERIOR OF VEHICLES (ENGINE, UNDERCARRIAGE AND TRANSMISSION WASHING IS PROHIBITED);
 - D. DUST CONTROL RUNOFF IN ACCORDANCE WITH PERMIT CONDITIONS;
 - E. ROUTINE EXTERNAL BUILDING WASH-DOWN, NOT INCLUDING SURFACE PAINT REMOVAL, THAT DOES NOT INVOLVE DETERGENTS;
 - F. PAVEMENT WASH-WATER (WHERE SPILLS/LEAKS OF TOXIC OR HAZARDOUS MATERIALS HAVE NOT OCCURRED, UNLESS ALL SPILLED MATERIAL HAD BEEN REMOVED); IF DETERGENTS ARE NOT USED;
 - G. UNCONTAMINATED AIR CONDITIONING OR COMPRESSOR CONDENSATE;
 - H. UNCONTAMINATED GROUNDWATER OR SPRING WATER;
 - I. FOUNDATION OR FOOTER DRAIN-WATER WHERE FLOWS ARE NOT CONTAMINATED;
 - J. UNCONTAMINATED EXCAVATION DE-WATERING;
 - K. POTABLE WATER SOURCES INCLUDING WATERLINE FLUSHINGS; AND
 - L. LANDSCAPE IRRIGATION.
- 7. UNAUTHORIZED NON-STORMWATER DISCHARGES: THE DEPARTMENT'S APPROVAL DOES NOT AUTHORIZE A DISCHARGE THAT IS MIXED WITH A SOURCE OF NON-STORMWATER, OTHER THAN THOSE DISCHARGES SPECIFICALLY, THE DEPARTMENT'S APPROVAL DOES NOT AUTHORIZE DISCHARGES OF THE FOLLOWING:
 - A. WASTEWATER FROM THE WASH-OUT OR CLEAN OUT OF CONCRETE, STUCCO, PAINT, FORM RELEASE OILS, CURING COMPOUNDS OR OTHER CONSTRUCTION MATERIALS;
 - B. FUELS, OILS OR OTHER POLLUTANTS USED IN VEHICLE AND EQUIPMENT OPERATION AND MAINTENANCE;
 - C. SOAPS, SOLVENTS, OR DETERGENTS USED IN VEHICLE AND EQUIPMENT WASHING; AND
 - D. TOXIC OR HAZARDOUS SUBSTANCES FROM A SPILL OR OTHER RELEASE.

WINTER EROSION CONTROL MEASURES

THE WINTER CONSTRUCTION PERIOD IS FROM NOVEMBER 1 THROUGH APRIL 15. IF THE CONSTRUCTION SITE IS NOT STABILIZED WITH PAVEMENT, A ROAD GRAVEL BASE, 75% MATURE VEGETATION COVER OR RIPRAP BY NOVEMBER 1 THEN THE SITE NEEDS TO BE PROTECTED WITH OVER-WINTER STABILIZATION. AN AREA CONSIDERED OPEN IS ANY AREA NOT STABILIZED WITH PAVEMENT, VEGETATION, MULCHING, EROSION CONTROL MATS, RIPRAP OR GRAVEL BASE ON A ROAD. LIMIT THE EXPOSED AREA TO THOSE AREAS IN WHICH WORK IS EXPECTED TO BE UNDER TAKEN DURING THE PROCEEDING 15 DAYS AND THAT CAN BE MULCHED IN ONE DAY PRIOR TO ANY SNOW EVENT. ALL AREAS SHALL BE CONSIDERED TO BE DENUED UNTIL THE SUBBASE GRAVEL IS INSTALLED IN ROADWAY AREAS OR THE AREAS OF FUTURE CANAL AND SEED HAVE BEEN LOAMED, SEEDED AND MULCHED. HAY AND STRAW MULCH RATE SHALL BE A MINIMUM OF 150 LBS./1,000 S.F. (3 TONS/ACRE) AND SHALL BE PROPERLY ANCHORED. THE CONTRACTOR MUST INSTALL ANY ADDED MEASURES WHICH MAY BE NECESSARY TO CONTROL EROSION/SEDIMENTATION FROM THE SITE DEPENDENT UPON THE ACTUAL SITE AND WEATHER CONDITIONS. CONTINUATION OF EARTHWORK OPERATIONS ON ADDITIONAL AREAS SHALL NOT BEGIN UNTIL THE EXPOSED SOIL SURFACE ON THE AREA BEING WORKED HAS BEEN STABILIZED, IN ORDER TO MINIMIZE AREAS WITHOUT EROSION CONTROL PROTECTION.

1. SOIL STOCKPILES

STOCKPILES OF SOIL OR SUBSOIL WILL BE MULCHED FOR OVER WINTER PROTECTION WITH HAY OR STRAW AT TWICE THE NORMAL RATE OR AT 150 LBS/1,000 S.F. (3 TONS PER ACRE) OR WITH A FOUR-INCH LAYER OF WOOD WASTE EROSION CONTROL MIX. THIS WILL BE DONE WITHIN 24 HOURS OF STOCKING AND RE-ESTABLISHED PRIOR TO ANY RAINFALL OR SNOWFALL. ANY SOIL STOCKPILE WILL NOT BE PLACED (EVEN COVERED WITH HAY OR STRAW) WITHIN 100 FEET FROM ANY NATURAL RESOURCES.

2. NATURAL RESOURCES PROTECTION

ANY AREAS WITHIN 100 FEET FROM ANY NATURAL RESOURCES, IF NOT STABILIZED WITH A MINIMUM OF 75% MATURE VEGETATION CATCH, SHALL BE MULCHED BY DECEMBER 1 AND ANCHORED WITH PLASTIC NETTING OR PROTECTED WITH EROSION CONTROL MATS. DURING WINTER CONSTRUCTION, A DOUBLE LINE OF SEDIMENT BARRIERS (I.E. SILT FENCE BACKED WITH HAY BALES OR EROSION CONTROL MIX) WILL BE PLACED BETWEEN ANY NATURAL RESOURCE AND THE DISTURBED AREA.

PROJECTS CROSSING THE NATURAL RESOURCE SHALL BE PROTECTED A MINIMUM DISTANCE OF 100 FEET ON EITHER SIDE FROM THE RESOURCE. EXISTING PROJECTS NOT STABILIZED BY DECEMBER 1 SHALL BE PROTECTED WITH THE SECOND LINE OF SEDIMENT BARRIER TO ENSURE FUNCTIONALITY DURING THE SPRING THAW AND RAINS.

3. SEDIMENT BARRIERS

DURING FROZEN CONDITIONS, SEDIMENT BARRIERS SHALL CONSIST OF WOOD WASTE FILTER BERMS AS FROZEN SOIL PREVENTS THE PROPER INSTALLATION OF HAY BALES AND SEDIMENT SILT FENCES.

4. MULCHING

ALL AREA SHALL BE CONSIDERED TO BE DENUED UNTIL AREAS OF FUTURE LOAM AND SEED HAVE BEEN LOAMED, SEEDED AND MULCHED. HAY AND STRAW MULCH SHALL BE APPLIED AT A RATE OF 150 LB. PER 1,000 SQUARE FEET OR 3 TONS/ACRE (TWICE THE NORMAL ACCEPTED RATE OF 75-LBS./1,000 S.F. OR 1.5 TONS/ACRE) AND SHALL BE PROPERLY ANCHORED. MULCH SHALL NOT BE SPREAD ON TOP OF SNOW. THE SNOW WILL BE REMOVED DOWN TO A ONE-INCH DEPTH OR LESS PRIOR TO APPLICATION. AFTER EACH DAY OF FINAL GRADING, THE AREA WILL BE PROPERLY STABILIZED WITH ANCHORED HAY OR STRAW OR EROSION CONTROL MATTING. AN AREA SHALL BE CONSIDERED TO HAVE BEEN STABILIZED WHEN EXPOSED SURFACES HAVE BEEN EITHER MULCHED WITH STRAW OR HAY AT A RATE OF 150 LB. PER 1,000 SQUARE FEET (3TONS/ACRE) AND ADEQUATELY ANCHORED THAT GROUND SURFACE IS NOT VISIBLE THROUGH THE MULCH.

BETWEEN THE DATES OF SEPTEMBER 1 AND APRIL 15, ALL MULCH SHALL BE ANCHORED BY EITHER PEG LINE, MULCH NETTING, ASPHALT EMULSION CHEMICAL TRAP OR WOOD CELLULOSE FIBER. WHEN GROUND SURFACE IS NOT VISIBLE THROUGH THE MULCH THEN COVER IS SUFFICIENT. AFTER NOVEMBER 1ST, MULCH AND ANCHORING OF ALL BARE SOIL SHALL OCCUR AT THE END OF EACH FINAL GRADING WORK DAY.

5. MULCHING ON SLOPES AND DITCHES













SLOPES SHALL NOT BE LEFT EXPOSED FOR ANY EXTENDED TIME OF WORK SUSPENSION UNLESS FULLY MULCHED AND ANCHORED WITH PEG AND NETTING OR WITH EROSION CONTROL BLANKETS. MULCHING SHALL BE APPLIED AT A RATE OF 230 LBS/1,000 S.F. ON ALL SLOPES GREATER THAN 8%. MULCH NETTING SHALL BE USED TO ANCHOR MULCH IN ALL DRAINAGE WAYS WITH A SLOPE GREATER THAN 3%. FOR SLOPES EXPOSED TO DIRECT WINDS AND FOR ALL OTHER SLOPES GREATER THAN 5% EROSION CONTROL BLANKETS SHALL BE USED TO ANCHOR MULCH IN ALL DRAINAGE WAYS WITH SLOPES 8%. EROSION CONTROL MIX CAN BE USED TO SUBSTITUTE EROSION CONTROL BLANKETS ON ALL SLOPES EXCEPT DITCHES.

6. SEEDING

BETWEEN THE DATES OF OCTOBER 15 AND APRIL 1ST, LOAM OR SEED WILL NOT BE REQUIRED. DURING PERIODS OF ABOVE FREEZING TEMPERATURES FINISHED AREAS SHALL BE FINE GRADED AND EITHER PROTECTED WITH MULCH OR TEMPORARILY SEEDED AND MULCHED UNTIL SUCH TIME AS THE FINAL TREATMENT CAN BE APPLIED. IF THE DATE IS AFTER NOVEMBER 15T AND IF THE EXPOSED AREA HAS BEEN LOCKED, FINALLY GRADED WITH AN UNIFORM SURFACE AND SEEDING CAN BE DORMANT SEEDED AT A RATE OF 3 TIMES HIGHER THAN SPECIFIED FOR PERMANENT SEED AND THEN MULCHED. DORMANT SEEDING MAY BE SELECTED TO BE PLACED PRIOR TO THE PLACEMENT OF MULCH AND FABRIC NETTING ANCHORED WITH STAPLES. IF DORMANT SEEDING IS USED FOR THE SITE, ALL DISTURBED AREAS SHALL RECEIVE 4" OF LOAM AND SEED AT AN APPLICATION RATE OF 5LBS/1000 S.F. ALL AREAS SEEDED DURING THE WINTER WILL BE INSPECTED IN THE SPRING FOR ADEQUATE CATCH. ALL AREAS SUFFICIENTLY VEGETATED (LESS THAN 75% CATCH) SHALL BE REVEGETATED BY REPLACING LOAM, SEED AND MULCH. IF DORMANT SEEDING IS NOT USED FOR THE SITE, ALL DISTURBED AREAS SHALL BE REVEGETATED IN THE SPRING. SEED TYPE SHALL BE WINTER RYE.

7. INSPECTION AND MONITORING

MAINTENANCE MEASURES SHALL BE APPLIED AS NEEDED DURING THE ENTIRE CONSTRUCTION SEASON, AT A MINIMUM, AFTER EACH RAINFALL, SNOW STORM OR PERIOD OF THAWING AND RUNOFF, THE SITE CONTRACTOR SHALL PERFORM A VISUAL INSPECTION OF ALL INSTALLED EROSION CONTROL MEASURES AND PERFORM REPAIR



NOT FOR CONSTRUCTION

REV.	BY	DATE	STATUS
C	SGD	03/30/2021	ISSUED FOR FINAL SUBDIVISION REVIEW
B	SGD	02/02/2021	REVISED BY TOWN AND PUBLIC INPUT
A	SGD	10/28/2020	ISSUED TO PLANNING BOARD FOR MAJOR REVISION REVIEW

THIS PLAN SHALL NOT BE MODIFIED WITHOUT WRITTEN PERMISSION FROM SEBAGO TECHNICS, INC. ANY ALTERATIONS, AUTHORIZED OR OTHERWISE, SHALL BE AT THE USER'S SOLE RISK AND WITHOUT LIABILITY TO SEBAGO TECHNICS, INC.





SEBAGO TECHNICS
75 John Roberts Rd.
Sullivan, ME 04196
South Portland, ME 04106
Tel. 207-200-2100
WWW.SEBAGOTECHNICS.COM

DETAILS OF:
IVY SUBDIVISION
ENDCLIFFE ROAD
KENNEBUNKPORT, MAINE

FOR:
IVY THREE, LLC
2 LIVEWELL DRIVE, SUITE 203
KENNEBUNK, ME 04043


DESIGNED	SAH
DRAWN	STI
CHECKED	SGD
DATE	4/13/2020
SCALE	NTS
PROJECT	10234

SHEET 7 OF 8



8' X 4' PRECAST BOX CULVERT
NOT TO SCALE

- NOTES:
1. COMPACT NATURAL FILL TO 95% OF THE STANDARD PROCTOR DENSITY. PROVIDE GRADATION AND COORDINATE WITH ENGINEER PRIOR TO PLACING.
 2. STONE/NATURAL FILL LAYER SHALL CONSIST OF ANGULAR RIPRAP (D50-6") MIXED WITH NATURAL STREAMBED MATERIAL TO FORM DENSE COMPACTED BASE. COORDINATE WITH ENGINEER.
 3. WORK WITHIN THE STREAM CHANNEL SHALL OCCUR DURING LOW FLOOD PERIODS AND SHALL NOT OCCUR WITHIN 72 HOURS OF ANY PREDICTED INCLEMENT WEATHER EVENTS.
 4. CONTRACTOR SHALL BE RESPONSIBLE FOR MAINTAINING FLOW THROUGH THE CULVERT CROSSING DURING CONSTRUCTION AND SHALL SUBMIT A WORK PLAN FOR THE ENGINEER'S APPROVAL.



NOT FOR CONSTRUCTION

C	SGD	03/30/2021	ISSUED FOR FINAL SUBDIVISION REVIEW
B	SGD	02/02/2021	REVISED BY TOWN AND PUBLIC INPUT
A	SGD	10/28/2020	ISSUED TO PLANNING BOARD FOR MAJOR REVISION REVIEW
REV	BY	DATE	STATUS


THIS PLAN SHALL NOT BE MODIFIED WITHOUT WRITTEN PERMISSION FROM SEBAGOTECHNICS, INC. ANY ALTERATIONS, AUTHORIZED OR OTHERWISE, SHALL BE AT THE USER'S SOLE RISK AND WITHOUT LIABILITY TO SEBAGOTECHNICS, INC.

SEBAGO
TECHNICS
www.sebagotechnics.com
75 John Roberts Rd.
Sullivan, ME 04196
South Portland, ME 04106
Tel. 207-260-2100

DETAILS
OF:
IVY SUBDIVISION
ENDCLIFFE ROAD
KENNEBUNKPORT, MAINE
FOR:
IVY THREE LLC
2 LIVEWELL DRIVE, SUITE 203
KENNEBUNK, ME 04043


DESIGNED	SAH
DRAWN	STI
CHECKED	SGD
DATE	4/13/2020
SCALE	NTS
PROJECT	10234

10234.Dwg, TAB 03



POST-DEVELOPMENT LEGEND

	WATERSHED BOUNDARY
	TIME OF CONCENTRATION
	REACH
	WATERSHED LABEL
	REACH
	STUDY POINT
	STORMWATER TREATMENT/DETENTION POND
	HSG #
	HSG #



NOT FOR CONSTRUCTION

C	SGD 03/30/2021	ISSUED FOR FINAL SUBDIVISION REVIEW	
B	SGD 02/02/2021	REVISED BY TOWN AND PUBLIC INPUT	
A	SGD 10/28/2020	ISSUED TO PLANNING BOARD FOR MAJOR REVISION REVIEW	
REV:	BY:	DATE:	STATUS:

THIS PLAN SHALL NOT BE MODIFIED WITHOUT WRITTEN PERMISSION FROM SEBAGO TECHNICS, INC. ANY ALTERATIONS, AUTHORIZED OR OTHERWISE, SHALL BE AT THE USER'S SOLE RISK AND WITHOUT LIABILITY TO SEBAGO TECHNICS, INC.

SEBAGO
TECHNICS
www.sebagotechnics.com
75 John Roberts Rd.
Suite 4A
South Portland, ME 04106
Tel: 207-260-2100

POST-DEVELOPMENT WATERSHED PLAN
OF:
IVY SUBDIVISION
ENDCLIFFE ROAD
KENNEBUNKPORT, MAINE
FOR:
IVY THREE, LLC
2 LIVEWELL DRIVE, SUITE 203
KENNEBUNK, ME 04043

DESIGNED	SAH
DRAWN	SAH
CHECKED	PDO
DATE	4/13/2020
SCALE	1" = 60'
PROJECT	10234

